Review Date: ____ / ____ / ____

CONDUIT INSTALLATION IN WALLS AND CEILINGS

Date Created: ____ / ____ / ____

Approved by:

Step	Job step	Hazards	Risks	Risk rating	Controls	Hierarchy of control	Residual risk
01	Note: If you are not deemed com	petent, you are not p	ermitted to perform a	any live te	sting whatsoever		
02	Check layout and mark out	Tripping and exposed nails	Failure to prevent trip hazards and piercing	MOD (C3)	Ensure areas in particular walkways are clear	Administrative	LOW (E3)
			hazards		Safety footwear to be worn	- PPE	
03	Install Conduit	Electrical Contact	Failure to prevent contact with live electrical	HIGH (B2)	Confirm any exiting installations are de- energised	Administrative	MOD (E2)
			components		Use only correctly tagged equipment		
04	Secure fixings and supports	Debris and Noise exposure	Failure to remove noise from drilling	MOD (B4)	Use minimum drilling speed consistent with effective work	Administrative	LOW (E4)
					Use goggles for eye protection	_ PPE _	
					Suitable Respirator and Hearing Protection		
					Ensure Drill bits are sharp		
					Implement Working at Heights SWMS		
05	Miscellaneous	Falling objects	Failure to remove the	HIGH	Wear a Safety Helmet	Administrative	MOD
			likelihood of have falling objects	(B2)	Restrict or Control Traffic	PPE	(E2)
		Falling	Risk of falling from height	HIGH (C1)	Implement Using Mobile Scaffolds SWMS	Administrative	MOD (E1)

|--|